



WESTFÄLISCHE
WILHELMS-UNIVERSITÄT
MÜNSTER

The KATRIN experiment

Status and commissioning



living.knowledge
WWU Münster

Philipp Chung-On Ranitzsch for the KATRIN collaboration
Institute for Nuclear Physics, Westfälische Wilhelms-Universität, Münster



(Tritium) β -decay and neutrino mass

β -decay: ${}^A_Z X_N \rightarrow {}^A_{Z+1} X_{N-1} + e^- + \bar{\nu}_e$



Tritium ${}^3\text{H}$:
 $E_0 = 18.6 \text{ keV}$
 $T_{1/2} = 12.3 \text{ y}$


Rhenium ${}^{187}\text{Re}$:
 $E_0 = 2.47 \text{ keV}$
 $T_{1/2} = 4.3 \cdot 10^{10} \text{ y}$

Holmium ${}^{163}\text{Ho}$ (EC):
 $E_0 = 2.8 \text{ keV}$
 $T_{1/2} = 4570 \text{ y}$

$$\frac{dN}{dE} = K F(E, Z) p (E_e + m_e)(E_0 - E_e) \sqrt{(E_0 - E_e)^2 - m(\bar{\nu}_e)^2}$$

MAC-E Filter

Magnetic **A**diabatic **C**ollimation and **E**lectrostatic Filter:



Magnetic guiding and collimation of e^-

- Transform $E_{\perp}$ to $E_{\parallel}$

$$\mu = \frac{E_{\perp}}{B} = \text{const.}$$

Electrostatic field for energy analysis


- Sharp transmission depending on:

- Emission angle
- Radius in at $B_{\min}$

Integrated energy resolution:

$$\Delta E = E \frac{B_{\min}}{B_{\max}}$$

The KATRIN experiment




KATRIN primary goal:

- Energy filter width: $\Delta E = 0.93 \text{ eV}$
- Measure neutrino mass with a sensitivity of $m(\nu) = 200 \text{ meV}$ (90 % C.L.)

KATRIN beyond $m(\nu)$:

- Search for eV- and keV-scale sterile neutrinos
- Right handed currents (w/ sterile neutrinos), Lorentz invariance, ...
- Technological advances in many fields

The KATRIN experiment




KATRIN primary goal:

- Energy filter width: $\Delta E = 0.93 \text{ eV}$
- Measure neutrino mass with a sensitivity of $m(\nu) = 200 \text{ meV}$ (90 % C.L.)

KATRIN beyond $m(\nu)$:

- Search for eV- and keV-scale sterile neutrinos
- Right handed currents (w/ sterile neutrinos), Lorentz invariance, ...
- Technological advances in many fields

The KATRIN experiment




Source section:
High intensity, highly
stable T_2 source
WGTS

Transport section:
Tritium retention by
a factor 10^{14}
DPS, CPS


Spectrometer and detector section:
Electron analysis and detection
PreSpec, MainSpec, FPD

The KATRIN experiment




WGTS delivery, Sept. 10th, 2015

The KATRIN experiment




Windowless gaseous tritium source (WGTS)

- T_2 source with 1.7×10^{11} Bq
- 10 m long, $\varnothing$ 9 cm tube
- T_2 gas, $p = 10^{-3} \dots 10^{-6}$ mbar
- Stable on 10^{-3} level
- Arrived on Sept. 10th 2015
- Installation progressing






The KATRIN experiment



Differential pumping section (DPS)

- Tritium retention by 10^5 by active pumping with 4 TMPs
- 5 superconducting solenoids
- Magnets set up & working at KIT
- Beam line assembly finishing up
- Integration into T_2 infrastructure

The KATRIN experiment







Cryogenic pumping section (CPS)

- Tritium retention $> 10^7$
- Cryo-pumping of residual gas
- 7 magnets @ 5.6 T
- Delivered to KIT on July 30, 2015
- Cool down is ongoing (currently < 200 K)



The KATRIN experiment



Spectrometer and detector section

Tandem spectrometer setup

Pre-Spectrometer

- Pre-filter $10^{10} \text{ e}^-/\text{s} \Rightarrow 10^3 \text{ e}^-/\text{s}$
- Used for R&D for Main Spec

Main Spectrometer


- Main energy analysis
- $\Delta E = 0.93 \text{ eV}$

Focal plane detector (FPD)

- 148 Pixel Si-PIN diode
- $\Delta E \sim 2 \text{ keV}$

Everything on site

Spectrometer and Detector commissioning



Two phases: SDS-I 2013; SDS-II(a+b): late 2014 to mid 2015

Subsystems:

- Main spectrometer
- Focal plane detector
- Angular selective e^- -source

Tests:

- Hardware, Software, Slow Control
- Transmission Properties
- Background

Spectrometer and Detector commissioning




Electron transmission properties

Mono-energetic, angular selective
electron gun

- fast non-adiabatic acceleration of e^-
in non-parallel $\vec{E}$ and $\vec{B}$ fields

Test the effect inside MS of

- electric potential
- magnetic field





Spectrometer and Detector commissioning

Electron Optics

Angular selectivity shown

- Width: $\Delta E \approx 1.2 \text{ eV} \approx E \frac{B_{\min}}{B_{\max}}$
 $E = 18.6 \text{ keV}; B_{\min} = 0.38 \text{ mT}; B_{\max} = 5 \text{ T}$

- Consistent with calculation



Spectrometer and Detector commissioning

Electron Optics

Angular selectivity shown



- Width: $\Delta E \approx 1.2 \text{ eV} \approx E \frac{B_{\min}}{B_{\max}}$
 $E = 18.6 \text{ keV}; B_{\min} = 0.38 \text{ mT}; B_{\max} = 5 \text{ T}$

- Consistent with calculation

Potential drop towards center


- $\Delta U = 0.3 \dots 1.0 \text{ V}$
- Consistent with simulations

Detailed analysis ongoing




Spectrometer and Detector commissioning

Background processes



Spectrometer and Detector commissioning


Background processes




Spectrometer and Detector commissioning

Background processes

- Most known and understood background sources excluded
- Remaining background level: $\sim 312 \pm 3$ mcps (design goal 10 mcps)
- Current working theory:
Internal radioactivity + neutral messenger particle
- Third commissioning phase in autumn



Systematics



5 major systematics contributions

Final states: new evaluation coming

(A. Saenz et al. PRL **84** (2000) 242)

Energy loss function: within specifications

(angular defined e-gun, paper in internal review)

Column density: Tests during STS III

(angular defined e-gun, Electron rate measurements, Raman spectroscopy...)


HV variations: within specifications

(Precision HV dividers, monitor spectrometer, Active post-regulation)

Elastic scattering

source of systematic shift	achievable / projected accuracy	systematic shift $\sigma_{\text{syst}}(m_{\nu}^2) (10^{-3} \text{ eV}^2)$
description of final states	$f < 1.01$	< 6
T^- ion concentration	$< 2 \cdot 10^{-8}$	< 0.1
unfolding of energy loss func. $f(\varepsilon)$		< 6
monitoring of column density ρd	$\Delta T/T < 2 \cdot 10^{-3}$	$< \frac{\sqrt{5 \cdot 6.5}}{10}$
	$\Delta \Gamma/\Gamma < 2 \cdot 10^{-3}$	
	$\Delta \varepsilon_T/\varepsilon_T < 2 \cdot 10^{-3}$	
	$\Delta p_{\text{inj}}/p_{\text{inj}} < 2 \cdot 10^{-3}$	
	$\Delta p_{\text{ex}}/p_{\text{ex}} < 0.06$	
background slope	$< 0.5 \text{ mHz/keV (Troitsk)}$	< 1.2
HV variations	$\Delta HV/HV < 3 \text{ ppm}$	< 5
WGTS potential variations	$\Delta U < 10 \text{ meV}$	< 0.2
WGTS mag. field variations	$\Delta B_S/B_S < 2 \cdot 10^{-3}$	< 2
elastic $e^- - \text{T}_2$ scattering		< 5
identified syst. uncertainties	$\sigma_{\text{sys, tot}} = \sqrt{\sum \sigma_{\text{sys}}^2} \approx 0.01 \text{ eV}^2$	


Commissioning of whole beam line




All sub-systems come online right about now

Combined commissioning:

- Interaction of different sub-systems
- Guide electrons from start to end
- Start with inactive source gases (H_2 , D_2)
 - Proposals in internal review
- Slowly increase tritium content (point of no return)



Conclusions



The KATRIN experiment

- Complete beam line on site since Sept. 2015
- Final assembly, site acceptance tests and commissioning ongoing
- Successful SDS commissioning phases already done → more to come
- Combined commissioning of whole system in late-2016
- First light (tritium) runs in 2017

Thank you!

